
Interpretation of Davis Keays Eagle Vein Area Defines Three Structural Corridors

VANCOUVER, BC / ACCESSWIRE / June 1, 2022 / Fabled Copper Corp. ("Fabled Copper" or the "Company") (CSE:FABL); (FSE:XZ7) announces the results of 2021 surface field work on its Muskwa Copper Project. See Figure 1 below.

Figure 1 - General Property Location


The Project is comprised of the Neil Property, the Toro Property and the Bronson property located in northern British Columbia. See Figure 2 below.

Figure 2 - Location Map



Peter Hawley, President, CEO reports; "A total of 19 specific areas were mapped and prospected during the 2021 field season and we started the New Year by reporting our findings on the Lady Luck occurrence in the south end of the Neil Property, followed by the Mac; the 8A, Harris, the 2a and 2b, the Creek, Keays south, Belcher Creek, the Magnum Mine UAV Done Mission, the Magnum, the Neil UAV Drone Mission, the Neil, EM-1, Ram Creek, Davis Keays Eagle UAV Drone Mission, sampling, surface geophysics, the underground inspection of the 6950 level of the Davis Keays Eagle Vein and now the structural interpretation of the Davis Keays area." See Figure 3 below.

Figure 3 - Neil Property, Davis Keays Eagle Location



Preamble

Minor follow-up exploration activity took place during the 1950s and early 1960s, with activity increasing significantly during the late 1960s and early 1970s. The work resulted in recognition of numerous copper occurrences within the Neil Property, the most significant of which are the Magnum Vein (Churchill Copper) and the Eagle Vein (Davis Keays). The Lady vein system at the Lady Luck Occurrence also received minor underground development work from 1969 - 1970. See Photo 1 below

Photo 1 - Neil Property, Davis Keays Eagle Mine



Davis-Keays Mine Circa 1970

More details on the past history, 2021 UAV drone mission, sampling and surface geophysics have been made public in the April 27th, May 4th, May 11th and May 25th releases.


The purpose of the 2021 structural survey over the Davis Keays area was threefold;

- i) Present preliminary structural interpretations that integrate field observations with high resolution photogrammetry imagery datasets and elevation models.
- ii) Review structural data collected at each of the two occurrences
- iii) Present a generalized structural interpretation that describes key features controlling copper mineralization.

All maps and imagery were drafted in the NAD83 (CSRS) datum and projected to UTM zone 10. A Google Earth TM .kmz file also performed which provided geotagged photographs taken at each mapping locality on the Eagle vein(s).


Coverage was restricted to the western slopes in the vicinity of the historic switchback road constructed over the vein during historic development and mining. Seventy-one structural measurements of bedding, cleavage, fold axes and veins were taken and 49 station geotagged photographs documented key features at each locality reviewed. All mapping data were plotted on high resolution orthomosaic imagery available for the site. See Figure 4 below.

Figure 4 - Orthomosaic Photo with Structural Measurements of Davis Keays Area



Digital elevation data were used to create a series of hillshade models generated at different sun azimuth angles. Different sun azimuth angles aid interpreting the location of key structural features including folding, bedding form lines, vein faults and potential thrust faults. See Figure 5 below.

Figure 5 - Hill Shade Model with Diabase Dikes and Quartz Veins Plotted



The orthomosaic was also reviewed in 3-D to better understand the location of veining and folding present in the Davis-Keays target.

Lineament interpretations were carried out to better understand the location of faults within known copper mineralized zones. Stratigraphic contacts were not mapped with enough confidence to be generate a lithological map for the area, however two main stratigraphic units were observed.

Numerous discrete quartz - iron mineralization veins were mapped in detail. See Photo 2 below.

Photo 2 - Quartz - Iron Mineralized Veins Davis Keays Area



In addition to mineralized veining two other types of mineralization were observed;

- 1. Quartz Sulphide mineralized breccia with a siltstone host and
- 2. Sulphide vein network within siltstone units, See Photos 3 and 4 below.

Photo 3 - Quartz Sulphide Breccia (a) and Breccia Photo 4 - Sulphide Vein Network (b)



In addition, mineralized quartz - carbonate veining overprinted by compressive deformation associated with regional thrusting was studied, See Figure 5 below.

Photo 5 - Compression Deformation, Davis Keays Area



The results of the structural studies clearly defined three preferred structural corridors, one of which corresponds to the underground Davis Keays, Eagle Vein workings. At this time not enough work or observations have to made to determine if there is an association with the mineralized veining and diabase dikes. See Figure 6 below.

EAGLE 2021 UNKNOWN WHETHER VEINING OCCURS WITH DIABASE STRUCTURAL CORRIDORS PROJECTION: NAD83 (CSRS) zone to - EAGLE_THRUST_INFERRED EAGLE_STRU_CORR EAGLE_VEINS ■ EAGLE_DIABASE **UNTESTED BUT** - EAGLE_LIN_NE **INACCESSIBLY STEEP** EAGLE_FOLD AXES_TRACE POSSIBLE CONTINUITY EAGLE_FORM UNDER INTERPRETED EAGLE_CLEAVAGE THRUST EAGLE_VEIN

Figure 6 - Structural Corridors, Davis Keays Area

Detailed observation of the high resolution Hillshade photo of the Davis Keays area clearly defines structural liniments which correspond to some of the mineralized features observed in the field. See Figure 7a for hillshade liniments and Figure 7b for liniments outlined in red.

Figure 7a - Shade Relief Liniments, Veining?





Figure 7b - Red line traces of Liniments




This led to close observation of the other side of the mountain where the eagle vein was observed and the same liniments associated with quartz veining was clearly evident as shown by the yellow dashed traces. See Photos 6, 7 below.

Photo 6 - Eagle Vein




Photo 7 - Other quartz veins near Eagle vein



Due to this correlation from both sides of the mountain, further detailed observations were made of the northeast area, See Figure 8 and box outline of detailed study area

Figure 8 - Detailed Study Area




This magnified observation of the northeast side of the mountain clearly show and defines the locations and strikes of at least 5 vein sets in addition to that of the eagle vein and all having a similar attitude. See Photo 8a for detailed photo of vein sets and Photo 8b of vein sets outlined in red trace.

Photo 8a - 5 Clearly Defined Vein Sets



Photo 8b - Red Trace Over Vein Sets



Looking at the structural kinetics we see both the macro scale slippage between vein sets, see Photo 9A below and the same movement in micro scale in the vein and replacement mineralization, see Photo 9b below.

Photo 9a - Macro Scale -Slippage in Vein Sets



Photo 9b - Micro Scale - Slippage



Going Forwards

All the various types of surveys performed on the Davis Keays area come to one general conclusion. The Davis Keays area is composed of numerous mineralized vein sets within a clearly defined structural corridor of which the eagle vein is only one that has seen extensive concentration of work both on surface and underground.

The 2022 field exploration program will follow up on this important findings but in addition to this, the Davis Keays area is Fabled Copper's first priority drill target to test the multi vein sets encounter during 2021 exploration program.

QA QC Procedure

Analytical results of sampling reported by Fabled Copper Corp represent rock samples submitted by Fabled Copper Corp staff directly to ALS Chemex, Vancouver, British Columbia Canada. Samples were crushed, split, and pulverized as per ALS Chemex method PREP-31, then analyzed for ME-ICP61 33 element package by four acid digestion with ICP-AES Finish. ME-GRA21 method for Au and Ag by fire assay and gravimetric finish, 30g nominal sample weight.

Over Limit Methods

For samples triggering precious metal over-limit thresholds of 10 g/t Au or 100 g/t Ag, the following is being used:

Au-GRA21 Au by fire assay and gravimetric finish with 30 g sample.

Ag-GRA21 Ag by fire assay and gravimetric finish.

Fabled Copper Corp. monitors QA/QC using commercially sourced standards and locally sourced blank materials inserted within the sample sequence at regular intervals.

About Fabled Copper Corp.

Fabled Copper is a junior mining exploration company. Its current focus is to creating value for stakeholders through the exploration and development of its existing copper properties located in northern British Columbia. The Muskwa Project comprises a total of 76 claims in two noncontiguous blocks and totals approximately 8,064.9 hectares, located in the Liard Mining Division in northern British Columbia.

Mr. Peter J. Hawley, President and C.E.O.

Fabled Copper Corp. Phone: (819) 316-0919 peter@fabledcopper.org

For further information please contact:

info@fabledcopper.org

The technical information contained in this news release has been approved by Peter J. Hawley, P.Geo. President and C.E.O. of Fabled, who is a Qualified Person as defined in National Instrument 43-101 - Standards of Disclosure for Mineral Projects.

The Canadian Securities Exchange does not accept responsibility for the adequacy or accuracy of this release.

Certain statements contained in this news release constitute "forward-looking information" as such term is used in applicable Canadian securities laws. Forward-looking information is based on plans, expectations and estimates of management at the date the information is provided and is subject to certain factors and assumptions, including, that the Company's financial condition and development plans do not change as a result of unforeseen events and that the Company obtains any required regulatory approvals.

Forward-looking information is subject to a variety of risks and uncertainties and other factors that could cause plans, estimates and actual results to vary materially from those projected in such forward-looking information. Some of the risks and other factors that could cause results to differ materially from those expressed in the forward-looking statements include, but are not limited to: impacts from the coronavirus or other epidemics, general economic conditions in Canada, the United States and globally; industry conditions, including fluctuations in commodity prices; governmental regulation of the mining industry, including environmental regulation; geological, technical and drilling problems; unanticipated operating events; competition for and/or inability to retain drilling rigs and other services; the availability of capital on acceptable terms; the need to obtain required approvals from regulatory authorities; stock market volatility; volatility in market prices for commodities; liabilities inherent in mining

operations; changes in tax laws and incentive programs relating to the mining industry; as well as the other risks and uncertainties applicable to the Company as set forth in the Company's continuous disclosure filings filed under the Company's profile at www.sedar.com. The Company undertakes no obligation to update these forward-looking statements, other than as required by applicable law.

SOURCE: Fabled Copper Corp.